


AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT		1. CONTRACT ID CODE	PAGE OF PAGES 1-9
2. AMENDMENT/MODIFICATION NO. A003	3. EFFECTIVE DATE August 31, 2020	4. REQUISITION/PURCHASE REQ. NO. PR9108001	5. PROJECT NO. (If applicable) 19PK400-20-Q-5044
6. ISSUED BY CODE Contracting Officer Department of State U.S. Consulate General Karachi.		7. ADMINISTERED BY (If other than Item 6) CODE	
8. NAME AND ADDRESS OF CONTRACTOR (NO., street,city,county,State,and ZIP Code) Offerors		9a. AMENDMENT OF SOLICITATION PR9108001	
		9b. DATED (SEE ITEM 11) August 31, 2020	
		10a. MODIFICATION OF CONTRACT/ORDER NO. 002	
		10b. DATED (SEE ITEM 13)	
11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS			
<p><input type="checkbox"/> The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers <input checked="" type="checkbox"/> is extended, <input type="checkbox"/> is not extended</p> <p>Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing Items 8 and 15, and returning <u>01</u> copies of the amendment;(b) By acknowledging receipt of this amendment on each copy of the offer submitted; or(c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers.</p> <p>FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment and is received prior to the opening hour and date specified.</p>			
12. ACCOUNTING AND APPROPRIATION DATA (If required)			
13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS, IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.			
	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.		
	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b)		
	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:		
X	D. OTHER (Specify type of modification and authority)		
E. IMPORTANT: Contractor <input checked="" type="checkbox"/> is not, <input type="checkbox"/> is required to sign this document and return <u>01</u> copies to the issuing office.			

14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)

The purpose of this amendment is as follow,

- 1- To amend proposal submission date from September 1st, 2020 to on/before September 4th 2020, 1200hrs.
- 2- Q&A from Pre-Proposal Site Conference attached.

Except as provided herein, all terms and conditions of the document referenced in SOW, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER (Type or print)		16A. NAME OF CONTRACTING OFFICER	
		Daniella Garreton	
15B. NAME OF CONTRACTOR/OFFEROR	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA	16C. DATE SIGNED
BY _____ (Signature of person authorized to sign)		BY  (Signature of Contracting Officer)	

NSN 7540-01-152-8070
Previous edition unusable

Standard Form 30 (revised 10/83)
Prescribed by GSA FAR (48 CFR) 53.243

Q&A – Pre-Proposal Site Conference PR9108001 19PK400-20-Q-5044:

1. Since it is a fix price contract and contractor has to work out and propose all the manpower and equipment requirement for this contract therefore it is very important that exact total measurement of all descriptions may be provided, so that each bidder has same information to work on and Consulate may have proper quotations / proposals, otherwise, for example it is likely that one bidder may assume the area to be 2000Sq.M whereas the other bidder assumes it to be 1000Sq.M and say the actual area comes to be 2100Sq.M and contract is awarded to the bidder with minimum price which has based his quotation upon the assumption of 1000Sq.M, than both Client and Contractor will be facing huge problems. Please note and respond.

Based on the existing condition of the walls, around 3000 square feet of wall needs to be raised from various parts of the perimeter wall to maintain requirement of 9 feet of height.

The wall height will need to be 9ft from the outside floor, so in some locations it may need to be raised and other locations it may not, depending on the outside floor dips or raises. In any event, it might be easier to say the following, “the perimeter wall will meet 9ft height standards, and will need to be raised to meet the 9ft requirement in areas where it does not.”

2. In item # 1 the unit of the quantity is written as Sft, whereas the total length of the wall is around 1500rft, hence if the height of the boundary wall is 9’-0”, then the sft quantity must be around 13500sft, in our opinion this is 1500 Rft instead of 1500 Sft please clarify.

a. The unit is RFT (running feet).

3. In item # 1(a) Drawing of the Host Nation approved Anti Climb Topping may be provided for the working.

a. The design shown during the site visit. It needs to be two coils of constantia wires with 1.5” angle iron support 10 feet apart. (picture below)



b.

4. In item # 1(c) Installation of Razor Teeth on Lower Doorway or Patio. At the time of visit Mr. Abdul Rab Ahmed Iqbal (Chief Engineer) told the Installation of Host Nation Anti Climb Topping with wire installed at Doorway or Patio.

a. Anti-climb measures needed above all doorways, patios and other climbable structures and pipes. The quantity measured as below:

- I. 3-Mehta = 128 feet.
- II. 1-Mehta = 128feet.
- III. 2-Bevelle = 60 feet.
- IV. 2-Golf = 120 feet
- V. 3-Golf = 80 feet

5. In item # 1(d) Relocation of Planters located at far end of Mehta Drive and far end of Golf Drive next to the wall , and move them off the wall or create distance. At time of visit Mr. Abdul Rab Ahmed Iqbal (Chief Engineer) told that create distance and fill distance of wall and planters with Concertina Wire and where the external planters cannot be relocated affix concertina or razor spikes to top edges to deter / deny access.

a. There are five planters next to 3-Mehta wall which needs to be moved 3 feet away using forklift.

b. There are five planters next to 3 Golf wall which needs to be moved 3 feet away using forklift.

6. In item # 2(a) For the Gates will have to be Re-Fabricated and RCC Columns will be Re-Casted, hence Drawing of Gates and Design of RCC Footing & Columns along with Gates may be provided.

a. The quantity of gates is as follows:

3-Mehta = 1, 1-Mehta = 1, 1-Bevelle = 1, 2-Bevelle = 2, 2-Golf = 2 and 3-Golf = 1 [Total = 8]

Design of gates is as below:



7. In item # 3(a) For the reinforcement of the doors it has been proposed that 5mm thick metal sheet may be installed on existing doors, however it is to be noted that fixing of 5mm sheet will have tremendous amount of stress on existing hinges, which may fall apart because of the excessive weight, hence metal door frame of MS Angle will have to be fixed for the doors, please advise.

a. The entrance doors are already reinforced by 5mm steel sheet from one side. The same needs to be done from outside.

b. The quantity of doors needs re-enforcement is as below:

3-Golf = 3, 2-Golf = 4, 2-Bevelle = 10, 1-Mehta = 3, 3-Mehta = 3 [Total = 23]

c. The doors which have a small opening on top (Picture below) needs to be covered with steel plates.



8. In Item # 3(d) says you require either 1/8" sheet fixing and at the same time complete safe heaven door is required, these are two totally different items which is actually required please clarify.

a. The 2-Golf Safe heaven door needs to be replaced with a new one. Design is similar to the other safe heaven doors.

We can just use a similar design as the other safe-haven doors, i.e., 5mm steel plated with horizontal cane bolt, and opens out not in. It will be slightly larger in size as the opening is larger, and the door frames will have to be reinforced. But the standards we want to meet are the same as the other reinforced doors that we are installing.



OBO-designed 15-Minute FEBR equivalent metal door w/ horizontal cane bolt



2x4 reinforced door frame, & horizontal cane bolt sleeves
1-Metha bedroom Safe Room

9. In Item # 4 the sizes of the window grills are required.

- a. Average size of window is 48" x 56".
- b. The quantity of windows in which new grills needs to be installed is as below:
3-Mehta = 17, 2-Bevelle = 17
- c. In addition, all windows of first floor needs to be covered with steel wire mesh to prevent climbing. The quantities are as under:
3-Mehta = 7, 1-Mehta = 8, 1-Bev = 12, 2-Bevelle = 22, 2-Golf = 9, 3-Golf = 20
10. In Item # 5(a) the Metal Mesh Cage Drawing of Pictures are required.



Example of enclosed emergency stairwell
Denying access to latch is critical

4. Relocation of concrete planters is not possible without a crane. Moreover if planters are relocated 3ft away from wall road will be occupied by these planters. what to do in this case?

a. They need to be relocated away from the wall using large fork lifter.

6. Thickness of metal plates for reinforcement of doors. Sheets be of MS or SS. Once door is reinforced it would become heavier then its frames would need to be replaced by new heavy frames. will you allow replacement of frames?

a. 5 mm. Yes, we will allow the replacement of frames if it is needed to support the new heavier doors.

7. Specifications of window grills i.e gauge and size metal. either solid or hollow pipes?

a. Average size is 48" x 56". Solid 5/8" square bar spaced 6" apart in the frame.

8. Gauge of wire mesh around stairs?

a. 10

9. No of trees to be cut

a. Trees are not required to be cut completely. Only branches falling over the wall needs to be trimmed. Approximate trees with falling branches is 12.

Further clarifications for the contractors:

- a. The perimeter wall needs to be 9 feet from the ground and anti-climb will be installed above that.
- b. Walls where we already have spikes will remain in place and anti-climb measure will be installed along with it.
- c. There is no need to remove inside planters.
- d. Entrance door of 3-Golf (Up) needs to be replaced and installed to open on outside.